



MSG	Page(s)	Title
025A	1 - 15	FD05 Flight Plan Revision (pdf)
026	16 - 17	FD05 Mission Summary (pdf)
027	18 - 19	FD05 Transfer Message (pdf)
030A	20 – 21	FD5 EVA Status Items (pdf)
028A		FD04 MMT Summary (pdf - Electronic Only)

Approved by FAO: Linda Delapp

Last Updated: Jun 12 2007 11:27AM GMT JEDI (Joint Execute package Development and Integration), v2.04.0003

1	MSG INDEX	
2 3 4 5 6 7 8 9	MSG NO. 025 026 027 028 029 030	TITLE FD05 Flight Plan Revision FD05 Mission Summary FD05 Transfer Message FD04 MMT Summary (Electronic Only) PAO Event Summary Message: CBS NEWS, KFOX-TV, KTSM-TV FD5 EVA Status Items
11 12 13 14 15	the pre M	quires camera B be routed to ISS on video channel 92 (Monitor 2) to support T translate survey operation. CCTV monitor 2 will need to be left on overnight. ving steps need to be added to the flight plan before crew sleep.
16 17	In <u>PRE-SI</u>	LEEP ACTIVITY - FLIGHT DECK LIST perform step 7 with the following deltas A3 TV MON 2 - ON
18 19 20 21		A7 TV PWR CNTR UNIT - MNA VID OUT MON 2 pb - push IN B pb - push
22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51		R12 √VPU PWR - ON (LED on) √Green Jumper - ISS

2. Flight Day 5 Exercise Constraints:


The table below summarizes the Shuttle and ISS exercise constraints for today. Except as noted, these constraints are also denoted in your timelines for your reference.


Activity	Exercise Constraints					
	Shuttle	ISS				
SABB DEPLOY TO 1 MAST BAY*	No exercise after SABB latches are open until SAW is deployed at least 1 mast bay	No unisolated exercise allowed after SABB latches are open until SAW is deployed at least 1 mast bay (only CEVIS and TVIS allowed)				
S4 SAW DEPLOY	No exercise during SAW latch or deploy/retract motor or EVA driven operations	No exercise during SAW latch or deploy/retract motor or EVA driven operations				
MT TRANSLATION*	No exercise allowed during MT translations (latch transition, unlatched with brakes on, UMA translating and MT translations)	Exercise constraints are as follows during MT translations (latch transition, unlatched with brakes on, UMA translating and MT translation):				
		The following are allowed in conjunction or separately: TVIS/IRED/CEVIS TVIS/IRED/SM ERGOMETER SM Ergometer rate limited to 60 RPM. CEVIS and SM Ergometer not allowed together.				


^{*} The exercise constraints for these tasks are not reflected in your timelines since they occur during crew sleep.


3. REPLACE PAGES 2-14, 2-16, AND 3-44 THROUGH 3-53.


FD0					······		- -	.,,,,,,,	11.	l			06	5/12/0	7 06:1	14:06 	 	REP	LANNED
$\beta = 51$		12 13 2 13	14 1,4 1	15 5	1,6	16	1,	17 7	1	. 8	8	1	.9 2	2 20		21 2 _, 1	2;2 2,2	2 2,3	23 004,/
MET	Day 003		 			1	1 1		3 1	1 3	1 C	X X				<u>.lll</u>		c i	
S T S	CDR STURCKOW	SLEEP	POST SLE	EEP	A 4 9 %		A 0 0 %		A 4 9 %	Α	0 W	F E R	MEAL		0FF	DUTY	MXFEF U	OPS W N C I 5 T	EXERCISE
	PLT/R2/M1 ARCHAMBAULT	SLEEP	POST SLEEP		C I I A C I	POST SLEEP	1 1 A 0 0 %	C T M U I W E N P C C R V D N A M R A C 4 T T	3 A 4 9 %	Α	1 M 0 N 0 V % R		MEAL		OFF	DUTY	SRMS RTRCT VIEW	SSRMS WS2 CNFO XLAT	XFER OPS
	MS1/EV3/R1 FORRESTER	SLEEP	POST SLEEP		1 # 4 9	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	1 1 A 0 0 %		3 A 4 9 %	3 A	0 >	N2 (FER INIT	MEAL		OFF	DUTY	PMDIS	EXERCI	SE E_LK PREP
1 1 7	MS2/EV4/M2 SWANSON	SLEEP	POST SLEEP		OST 4 EEP 9	POST	1 1 A 0 0 %	N R	41	MU A	1 0 0 8	MDIS	MEAL	OFF DUTY				E_LK PREP	
	MS3/EV2/R1 OLIVAS	SLEEP	POST SLE	EP	A 1 S <i>P</i> P 4 R 9 N %	\ 	1 1 A 0 0 %			MU Ā	1 0 0 %	M C I U	MEAL		OFF	DUTY	SRMS RTRCT VIEW		EXER CISE
	MS4/EV1 REILLY	SLEEP	POST SLE	EP	A 1 S A P 4 R 9 N %	POST SLEEP	1 1 A 0 0 %		3 A 4 9 %	3 A			MEAL		0FF	DUTY	FOOD XFER	POST EVA 1 TOOL CNFG	XFER OPS
D N	FE-2 WILLIAMS	SLEEP	POST SLEEP	SVP SRRDPC RFE MYP S*	P S V A E S O 4 P C A 9	AS AS AS OC	1 1 A 0 0	M V S N R S V F C R Y # *	3 A 4 SS 9 %	c 3 A	1 0 0 %	M E T X	MIDDAY-MEAL F	T S R / A U C		Н/0		TVIS	н / 0
E X P	ISS CDR ЮРЧИХИН	SLEEP	POST SLEEP	PREP WORK	P 2 R 5 E 7	Ві	кд-п	x0-C01-	CLSOU	T15	•	1	MIDDAY-MEAL			ΦΓБ CB CDR RCVRY		CEVIS	RED
- 1 5	FE-1 KOTOB	SLEEP	POST SLEEP	PREP WORK	P	-C01-CL	SOUT	T	PA C	x0 01 60UT		XFER NIT	MIDDAY-MEA	-		PMC FE1	RED	SSRMS WS2 CNFO XLAT	CEVIS
U P	FE-2 ANDERSON	SLEEP	POST SLEEP	PREP WORK	C P P S G M M E G D D T B I I U A S S P	PMDIS .	ADAP	T B BS		ADAPTA	ATIO	ON I	MIDDAY-MEAL	ADAPT	Line	н/о	, , , , ,	(FER	CTRACPMC H / 0
	SSRMS DAY/NIGHT								-WS2	PDGF2									
S T S	ORBIT W -171 TDRS E -46 Z -275	57	57 58 59				<u> </u>	60	- 	, -	→	61			52 		63	 	64
	ORB ATT NOTES	BÍAS	-XLV -ZVV	*1A CAMEI		XPOP —	, r.c	#3A C	XPO 3A CA AMERA	P ——— MERA S	CONI	FIG #TE	:RM		—— ВІА	AS -XLV -ZVV			
							- NU	EXERCI)E —		1_		FIT DIA						





























MSG 026 (15-0402) - FD05 MISSION SUMMARY

Page 1 of 2

```
1
     Good Morning Atlantis!
 2
     Congratulations on an exceptional EVA yesterday! We look forward to another great day in
     space with the 1A/3A SAW deploy. Enjoy the well deserved time off today.
 3
 4
 5
    YOUR CURRENT ORBIT IS: 183 X 179 NM
 6
 7
    NOTAMS:
8
9
    MORON (MRN) - CLOSED
    WAKE ISLAND (WAK) - CLOSED
10
     GOOSE BAY (YYR) - RWY 08/26 CLOSED
11
12
    KEFLAVIK (IKF) - UNUSABLE
13
     RIO GALLEGOS (AWG) - UNUSABLE
14
15
    NEXT 2 PLS OPPORTUNITIES:
16
17
    EDW22 ORB 64 - 3/23:34 (SCT250 250/18P28)
18
     EDW22 ORB 80 - 4/23:54 (SKC 240/15P25)
19
20
    OMS TANK FAIL CAPABILITY:
21
22
    LOMS FAIL: NO
                                         R OMS FAIL: NO
23
24
    LEAKING OMS PRPLT BURN:
25
    L OMS LEAK: ALWAYS RETROGRADE
26
27
    R OMS LEAK: ALWAYS RETROGRADE
28
29
    OMS QUANTITIES(%)
30
31
    L OMS OX = 31.0
                       R OMS OX = 33.0
32
           FU = 30.8
                              FU = 32.5
33
34
    SUBTRACT I'CNCT COUNTER FOR CURRENT OMS QUANTITIES
35
36
    DELTA V AVAILABLE:
37
38
    OMS
                                 333 FPS
39
     ARCS (TOTAL ABOVE QTY1)
                                  47 FPS
40
    TOTAL IN THE AFT
                                 380 FPS
41
    ARCS (TOTAL ABOVE QTY2)
42
                                  81 FPS
43
    FRCS (ABOVE QTY 1)
                                  29 FPS
44
                                    81 %
45
    AFT QTY 1
46
    AFT QTY 2
                                    43 %
47
48
49
50
```

MSG 026 (15-0402) - FD05 MISSION SUMMARY Page 2 of 2

<u>SYSTEM</u>	<u>FAILURE</u>	<u>IMPACT</u>	WORK AROUND
COMM/INST	Camera A focus stuck. Camera regained focus capability after a period of time.	Cannot focus camera. Fuzzy video while in this state.	None. Camera A is working at this time. Use alternate camera if failure reoccurs or power camera A off. Wait for 2 hrs then try to focus camera again.
EVA1	EMU 3004 (EV2's EMU) Failed CO2 Sensor	Crew received CO2 sensor message on repress	EMU remains GO for EVA with this sensor down. Crew is prime for CO2 monitoring.
EVA2	EMU 3004 (EV2's EMU) Cooling Suspect	Degraded cooling may have attributed to CO2 sensor failure.	If cooling remains suspect, may require EV2 to use EMU 3006 (EV4's EMU)
EVA3	ISS Crew Lock In-flight Refill Unit (IRU) Pump Failed to Reach Nominal Supply Pressure.	None. IRU quantity indicated adequate water fill.	If pump degrades further, shuttle airlock could be used to recharge EMU water tanks
EVA4	PGT Power Offs during EVA1	PGT unable to sustain operations under moderate to high torque loads	Use new batteries launched on 117.

MSG 027 (15-0403) - FD05 TRANSFER MESSAGE

Page 1 of 8

Good morning crew,

Welcome to another installment of "This is your Transfer List Update". Today we've made a few minor updates to both lists and also added two new transfer items for return. Have a great day and enjoy.

The Transfer List Excel file, FD05_TransferList_STS117.xls, is located on the KFX machine in **C:\OCA-up\transfer**.

For ISS, the Transfer List Excel file, FD05_TransferList_STS117.xls, is located in **K:\OCA-up\transfer**.

Transfer Notes

• We've added the EVA Transfer Bag as Item 801 to the real-time return section of the return tab. It will be stowed in 5 MLE Bag A, which may displace some foam. Any excess foam may be relocated to Bag F or the airlock. If stowed in the airlock, bundle it together and restrain it to the handrails.

 As a reminder please use Shuttle Air to Ground 2 for the transfer briefs at the end of the day.

Questions/Answers for the crew

 On FD03 you called down items 7.1 – 7.12 were complete. Were these items unpacked from the 0.5 CTB (ref. Item #7) and stowed by the ISS crew? Or, is the bag just across the Hatch?

Similarly, have Clay and Suni unpacked items 20.2 – 20.7 from Bag 20?

• Can you confirm that items 701, 701.1, and 701.2 were completed on FD03? Clay indicated they had been transferred to the Shuttle Middeck.

• During the FD03 Transfer calldown, you reported Clay's Bracelet-M Device (Transfer List Item #26) was stowed in his Каюта. Was that the TESS in the Lab or a Каюта in the Service Module?

• Item #23 (Blood Collection Kit) should not fit in LAB1O2_B2 until Return Bag 405 is removed. On FD03 you called down item #23 was complete. Was Return Bag 405 also transferred? Or, did you stow item #23 in a different location?

MSG 027 (15-0403) - FD05 TRANSFER MESSAGE Page 2 of 8

1	Choreography (items for transfer today)
2	TO ISS:
3	Item 12: A31p 60 GB Hard Drives
4	Item 30: ARMS/GLOVES/LEG RINGS 0.5 CTB
5	Item 31: [Clay's] ECOK in mesh bag
6	
7	FROM ISS:
8	Item 404, 404.2, 404.3, 404.16: P/TV Resupply 0.5 CTB and contents (transfer when
9	ops complete)
10	Item 410: LA's old LCVG 0.5 CTB
11	Item 411: QDM/Leader Panel 0.5 CTB
12	Item 411.3 and 411.4: Pack returning PMDIS and TRAC CDs after Clay's CD copy
13	activities.
14	Item 602 and 616: Nickel Removal Assembly (NiRA) with Cushion
15	Item 603: A31p Laptop
16	Item 606: 12A.1 CD Transfer Case
17	Item 609: Condensate Tank CWC Water Samples
18	Item 610, 611, 612, 613, 614, 615: Returning Food 0.5 CTBs
19	Diago in comparate unlink name of fillows.
20	Please incorporate uplink pages as follows:
21 22	In RESUPPLY tab
23	Replace Page(s): 7
23 24	Replace Page(5). I
2 4 25	In RETURN tab
26	Replace Page(s): 1, 2, 3, 5, 8 (note: item 603 was bumped from page 2 to 3. As such,
27	please replace page 3 even though there were no technical changes).
28	picase replace page 5 even though there were no technical changes).
29	Changes to the Transfer List are detailed below.
30	RESUPPLY
31	Item 27.2: Updated Qty
32	The second state of the se
33	RETURN
34	Item 403: Updated Notes
35	Item 407.5: Updated Notes
36	Item 702: Updated Constraint
37	Item 801: New Item
38	Item 802: New Item
39	
40	
41	Call us with any questions and have a great day!
42	
43	- The Transfer Team
44	
45	
46	
47	
48	
49	
50	

MSG 030A (15-0406A) - FD5 EVA STATUS ITEMS

Page 1 of 2

Great job on the EVA vesterday! We have a few follow up items for you.

1 2 3

4

5

6

PGT Battery Plan: We believe the PGT power off anomaly that occurred during the EVA might be attributed to a low battery voltage when under a load. As a precaution, we are changing our logistics plan to start using the new PGT batteries you transferred to ISS in your EVA Systems Transfer Bag. Please make the following pen and ink changes to the PGT Battery s/n column on your STS-117 Consumables Tracking Cue Card.

7 8

```
9
       EVA 2 – FD 6
10
       EV3: <del>5013</del>
                       1005
```

11

EV4: 5014 12 EVA 3 - FD 8

13

14 EV1: 5011

15

EV2: 5012 1004

16 17

EVA 4 – FD 10

18 EV3: 5013 EV4: 5014

1005 1006

1006

19 20

> The change of PGT batteries also affects your STS-117 Battery Recharge Plan. On the cue card, for FD 6, please charge PGT Batteries s/n 1005 and 1006 instead of 5013 and 5014.

23 24

21

22

Because these new batteries have not received a top-off charge since launch, we request you perform a voltage check as part of Tool Config to verify the voltage is above 36V.

25 26 27

28

29

30

31

Questions for Danny:

We believe the failure of your EMU CO2 sensor may be related to you being warm during the EVA. In order to help diagnose the issue, can you tell us when you first noticed your EMU was running warm? Did any actions (TCV positions, etc.) make things better or worse? Did the EMU run warm throughout the EVA? Can you tell us what TCV settings you used during the EVA?

32 33 34

35

38

39

40

Regarding the shiny spot on the left heel guide of the APFR, did it appear to you to have a sharp edge or have any raised burrs?

36 37

P6 WIF Inspection:

It has recently been identified that fasteners (circled in photo below) holding the WIF baseplates onto P6 could be loose. Note that the suspect fasteners are on the baseplate not the actual WIF itself. P6 WIFs 1 through 12 are suspect. You are using P6 WIF 11 for temp stowage of an APFR between EVA 2 and 3.

41 42 43

44

45


46

In addition to the usual pull test to confirm the APFR is fully secure, please do the following:

- Confirm that these 4 bolts are present and visually secure (no gap)
- Firmly push and pull on the installed APFR in order to confirm the 4 bolts and baseplate is completely secure.
- Call MCC with the results.

- 49 No tethering of the APFR is required after it is installed.
- 50 If WIF 11 is found to be loose, we will use P6 WIF 4A instead.
- 51 Only temp stowage of APFRs in these WIFs allowed for now - no ingressed APFR ops.

MSG 030A (15-0406A) - FD5 EVA STATUS ITEMS Page 2 of 2



MSG 028A (15-0404A) - FD04 MMT SUMMARY Page 1 of 3

FD4 MMT Crew Summary

The MMT met today to discuss mission progress, review the FD 2 inspection and FD 3 RPM photography, and discuss the Port OMS Pod blanket. As expected preflight, the MMT agreed with the recommendation to add two mission extension days and an EVA 4 to accomplish additional ISS tasks. The team appreciates your hard work and enjoyed following your progress today with the S3/S4 truss install and EVA 1.

Imagery/Debris Assessment Team:

The imagery and debris assessment teams have completed their review of the FD2 inspection data and FD3 RPM photography and have concluded that no Focused Inspection with OBSS is required. The team has reviewed all the LDRI data and cleared the RCC (starboard wing, port wing, and Nosecap) for entry.

The FD3 RPM data review has been completed and all TPS is clear for entry except for two protruding gap fillers and one tile area near the outboard edge of the port ET door which will likely be cleared tomorrow. One of these gap fillers is near the arrow head tile directly aft of the nose landing gear door and the other is on an aft tile forward of the bodyflap. Aerothermal analysis including the possible tripped flow downstream of these gap fillers continues. Based on the data obtained through FD 4, the team does not currently believe that any gap filler removal is required. A summary of the gap fillers and minor tile damage are shown in the figures below.

There are two areas where adequate data was not obtained for the TPS inspections including an area around Window 5&6 and the Right Inboard Elevon. These areas had shadows that obscured the areas of interest and additional imagery for these areas may be requested using ISS or SRMS assets.

Port OMS Pod Blanket:

The aero thermal analysis was discussed today and indicates that the entry thermal environment will result in localized temperatures inside the exposed cavity that exceed the OMS pod graphite epoxy structure certification limits. The heating is predicted to be slightly higher in this area than past flights with similar damage because the blanket extends up into the flow resulting in increased heat transfer in this cavity. The flow in this area is very difficult to model, thus certain best estimate engineering assumptions had to be applied in order to accurately model the heating.

Based on this preliminary thermal analysis and the limited test data available for this type of graphite composite structure, the MMT decided that the TPS is suspect for this area and the blanket will require a repair prior to deorbit/entry. This decision was based on the potential for thermal structural concerns only, since the team has concluded that if the blanket dislodged during entry it would not be a debris source for the rudder speedbrake.

Team 4 has been working to develop a simple method for securing the blanket to its original position. The theory is that the blanket has a structural memory and will retain whatever position it is moved to. The preliminary EVA techniques access this area via the SRMS and WIF extension. The detailed EVA techniques and robotics will be provided as soon as the team completes their procedure review. Tomorrow the MMT will discuss whether this task will be added to EVA 3 on flight day 8 or EVA 4 on flight day 10.

SRB Quick look - Preliminary data review shows nominal SRB performance and no in-flight anomalies of the hardware have been identified. Visual inspection shows no major areas of concern and post flight hardware inspections are proceeding per the standard timeline. We expect to view the SRB video of the External Tank tomorrow at the MMT. All data obtained so far indicates that ET-124 performed extremely well.

Figure 1: Tile/Gap Filler Summary.




Figure 2 - Arrowhead Tile Gap Filler




Figure 3 : Port ET Door Tile



Figure 4: Starboard ET Door Tile




Figure 5: Gap Filler protruding on Aft Fuselage

